



सरदार वल्लभभाई राष्ट्रीय प्रौद्योगिकी संस्थान, सुरत
Sardar Vallabhbhai National Institute of Technology, Surat



ESTATE SECTION

PERCENTAGE RATE TENDER PAPER



TENDER: 1

PRICE BID

Name of work	:	Repairing work in Old CRC at SVNIT Campus, Surat.
Name of Contractor	:	
Tender Fee	:	₹.500=00
Class of Registration	:	E2 – Class & Above
Issue of tender	:	01/06/2018 to 20/06/2018.
Receipt of tender	:	26/06/2018 upto 5:00 p.m.

The Director, S. V. National Institute of Technology, Ichchhanath, Surat – 395 007.
☎ 91-0261-2259571, 2259582-84

Name of Work :- **Repairing work in Old CRC at SVNIT Campus, Surat.**

**SCHEDULE – B
(PWD SOR 2015-16)**

Sr. No	Quantity	Item Descriptions	Total Rate Including 1% Labour Cess		Per	Amount	
			₹.	Ps		₹.	Ps
1	70.00	Dismantling doors,windows,ventilators etc. wood or steel)shutters including chowkhats architraves,holdfasts and other attachment etc. Complete and stacking them all lead and lift. (ii) Exceeding 3 sqm. In area. SOR It:- 20013B , p/170 + 1 % L.C. (158 + 1.58 = 159.58)	159.58		NO.	11170.60	
2	1915.00	Providind and fixing M.S. Grills of required pattern to wooden frames of windows etc. With M.S. Flats at required spacings and frame alround, square or round bars with round headed bolts and nuts or by screws (A) Plain Grill. (upto 10 ton) SOS It :-10025A, P/101+ 1% L.C. (65.5 + 0.65 = 66.15)	66.15		K.G.	126677.25	
3	125.00	Providind and fixing window having extruded aiuminum Colour Powder Coated section frame main outer size 63.5 x 38.10 x 1.95 mm(of Jindal Section no. 4605,@ Wt. 1.094 Kg/Rmt), horizontal two track member size 61.85 mm x 31.75 mm x 1.20mm (of Jindal Section no.8687 @ wt.of 0.659 Kg/mt), vertical member of size 61.85mmx 31.75 mm x 1.30 mm (of Jindal Section no. 8758 @ wt. of 0.659 Kg/ mt.) with sliding shutters of horizontal member size 40 mm x 18 mm x 1.29 mm (of Jindal Sectoin no. 8949 @ wt. of 0.456 Kg/mt.) ,vertical member of size 40mm x 18mm x 1.29mm (of Jindal Section no.8947 @ wt.of 0.456 kg/mt/ Section no.8948, @ wt. 0.457 kg/mt.) with 5mm thick transparent bronze colour tinted float glass with powder coated aluminum fittings and fixtures and transparent silicon sealant glass fixing as per details etc. complete for window. SOR It.-11.34 , p/125 + 1 % L.C. (2012.00 + 20.12 = 2032.12)	2032.12		SMT.	254015.00	
4	1.00	Providing and fixing washbasin with single hole for pillar tap with C.I. Or M.S.	927.18		NO.	927.18	

Sr. No	Quantity	Item Descriptions	Total Rate Including 1% Labour Cess		Per	Amount	
			₹.	Ps		₹.	Ps
		Brackets painted white including sutting holes and making good the same but excluding fittings. (A) Vitreous China : (ii) Flrt Back washbasin 550 mm x v 400 mm size. (i) In white colour SOR It :-23018, p/191+ 1 % L.C. (918 +9.18 = 927.18)					
5	1.00	Providing and fixing pillar tap,capstan head, screw down high pessure with screw, shanks andback nuts. (i) 15 mm dia. SOR It :- 23029 A, P/192+ 1% L.C. (357 + 3.57 = 360.57)	360.57		NO.		360.57
6	1.00	Providing and fixing brass screw down stop cock tap. (A) 15 MMDIA. SOR It:- 23030A, p/193 + 1% L.C. (239 + 2.39 = 241.39)	241.39		NO.		241.39
7	1.00	Providing and fixing C.P. Brass waste for washbasin or sink. (A) 32MM DIA. SOR It:- 23020A, P/192+ 1% L.C. (79.40+0.79= 80.19)	80.19		NO.		80.19
8	1.00	Providing and fixing 2 Ft. Long P.V.C. Connection pipe for wash basin As per market rate + 1% L.C. (70 + 0.7=70.70)	70.70		NO.		70.70
9	1.00	Providing and fixing 0.9 mt. Long P.V.C. Waste pipe for wash basin As per market rate + 1% L.C. (40 + 0.4=40.4)	40.40		NO.		40.40
10	1.00	Providing and fixing 600mmx450mm bevelled edge mirror of superior glass mounted on 6mm thick A.C. Sheet or piywood sheet and fixing to wooden pluge with C.P. brass screws and washers. SOR It:- 23024. p/192 + 1% L.C. (525 + 5.25 = 530.25)	530.25		NO.		530.25
11	3.50	Providing and fixing 25 mm thick double polish marble stone of approved quality for platform, cup-board, urinal partition including rubbing, polishing and moulding etc. complete as per direction of engr. In charge. As per market rate + 1% L.C. (817+8.17=825.17)	825.17		SMT.		2888.10

Sr. No	Quantity	Item Descriptions	Total Rate Including 1% Labour Cess		Per	Amount	
			₹.	Ps		₹.	Ps
12	8.00	Providing and fixing 0.9 mt. Long P.V.C. Waste pipe for urinals. As per market rate + 1% L.C. (40 + 0.4=40.4)	40.40		NO.	323.20	
13	6.00	Dismantling doors, windows, ventilators etc. wood or steel)shutters including chowkhats architraves, holdfasts and other attachment etc. Complete and stacking them within all lead and lift. (ii) Exceeding 3 sqm. In area. SOR It:- 20013B , p/170 + 1 % L.C. (158 + 1.58 = 159.58)	159.58		NO.	957.48	
14	0.85	Providing and laying 18 to 20 mm thick granite stone as per already existing type and quality & colour over base of cement mortar 1:2 (1- cement : 2- fine sand) laid and jointed with gray cement slurry. As per R.A.+1% L.C.(912+9.12=921.12)	921.12		SMT.	782.95	
15	1.20	Providing and fixing 35 mm thick shutters for doors, windows and clearstory windows including black enamelled m.s. butt hinges with necessary screws. (A) Indian teak wood. (ii) Fully Panelled. (upto 10 ton) S.O.R. it. :-10005A,P/94+1% L.C. (3013 + 30.13 = 3043.13)	3043.13		SMT.	3651.76	
16	3600.00	Removing dry or oil bound distemper by washing and scrapping and sand papering the wall surface smooth including necessary repairs the scratches complete. SOR -18014, P-163+ 1% L.C. (7.10 + 0.07 = 7.17)	7.17		SMT.	25815.60	
17	1275.00	Extra over above item for removing dry oil bound distemoer on ceilings and sloping roofs. SOR -18015, P-163+ 1% L.C. (1.00 + 0.01 = 1.01)	1.01		SMT.	1287.75	
18	3600.00	Applying two coats of Birla or Asian acrylic lappy (putty) and two coats of primer of approved brand and manufacture on new wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other matter and sand	47.87		SMT.	172346.40	

Sr. No	Quantity	Item Descriptions	Total Rate Including 1% Labour Cess		Per	Amount	
			₹.	Ps		₹.	Ps
		papered smooth. (The agency must give 3 years written guarantee for which 10% Security Deposit of respective paint work only will be released after completion of 3 years from the date of completion of work) SOR -lt 19032, P - 168 + 1% L.C. (47.40 + 0.47 = 47.87)					
19	3600.00	Wall Painting (two coat) with plastic emulsion paint of approved brand and manufacture and of required shade on wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth. (The agency must give 3 years written guarantee for which 10% Security Deposit of respective paint work only will be released after completion of 3 years from the date of completion of work) SOR - 18031, P – 164 + 1% L.C (49.9 + 0.50 = 50.40)	50.40		SMT.		181436.40
20	275.00	Painting two coats (excluding priming coat) on new wood and wood based surface with enamel paint, interior to give an even shade including cleaning the surface of all dirt, dust and other foreign matter sand papering and stopping. SOR It:- 19011, p/166 + 1% L.C.(55.60 + 0.56 = 56.16	56.16		SMT.		15444.00
21	3550.00	Finishing wall with weather proof extirior emulsion paint on wall surface (2-coats) to give a required shape even shade after thoroughly brushing the surface to remove all dirt, and remains of loose powdered materials etc. complete. (The agency must give 5 years written guarantee for which 10% Security Deposit of respective paint work only will be released after completion of 5 years from the date of completion of work) SOR It:- 19031, p/168 + 1% L.C.(72 + 0.72 = 72.72)	72.72		SMT.		258156.00
22	140.00	Providing and fixing 25mm dia Stainless Steel selected good quality of pipe	476.72		RMT.		66740.80

Sr. No	Quantity	Item Descriptions	Total Rate Including 1% Labour Cess		Per	Amount	
			₹.	Ps		₹.	Ps
		including the cost of S.S. concil piece and S.S. socket with labour charges for fitting with NF screw of required size etc. complete. As per R.A.+ 1% L.C.(472+4.72=476.72)					
23	400.00	Supplying the curtain cloth of good selected quality with stitching labour in fixing "O" rings including the cost of ilet patti at the border etc. complete as per selection of Engineer In charge. As per R.A.+ 1% L.C.(284+2.84=286.84)	286.84		SMT.		114736.00
			Total		₹...		12,38,679.96
			Say		₹...		12,40,000.00

I/ We am/ are willing to carry out the work at _____ % above/below percent (should be written in figures and words) of the estimated rates mentioned above.

Amount of my/ our tender works out as under.

Estimated amount

Put to tender ₹. _____

Deduct _____% below ₹. _____

Net ₹. _____

In words _____

Estimated amount

Put to tender ₹. _____

Add _____% above ₹. _____

Total ₹. _____

In words _____

Note

1. All work shall be carried out as per Public Works Department Handbook and other specifications of PWD/CPWD/SVNIT or as directed.
2. All the columns is Scheduled be filled in ink and the total of the entries in the last column should be struck by the contractor under his signature.
3. Rates quoted include clearance of site (prior commencement of work and at its close) in all respects and hold good for work under all conditions, site, moisture, weather etc.
4. To be continued on additional sheets, if found necessary.

POSTAL ADDRESS OF CONTRACTOR

SIGNATURE OF CONTRACTOR

DATE: