



सरदार वल्लभभाई राष्ट्रीय प्रौद्योगिकी संस्थान, सुरत
Sardar Vallabhbhai National Institute of Technology, Surat



ESTATE SECTION

PERCENTAGE RATE TENDER PAPER



TENDER: 1

PRICE BID

Name of work	:	Terrace Water Proofing and China Mosaic work at Training & Placement Section, SVNIT Campus, Surat.
Name of Contractor	:	
Tender Fee	:	₹.500=00
Class of Registration	:	E2 – Class & Above
Issue of tender	:	29/11/2018 to 20/12/2018.
Receipt of tender	:	26/12/2018 upto 5:00 p.m.

The Director, S. V. National Institute of Technology, Ichchhanath, Surat – 395 007.

☎ 91-0261-2259571, 2259582-84

Name of Work :- Terrace Water Proofing and China Mosaic work at Training & Placement Section, SVNIT Campus, Surat.

**SCHEDULE – B
(PWD SOR 2015-16)**

Sr. No	Quantity	Item Descriptions	Total Rate Including 1% Labour Cess		Per	Amount	
			₹.	Ps		₹.	Ps
1	710.00	Dismantling tiled of stone floors laid in mortar including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift SOR It:- 20005 , p/169 + 1 % L.C. (30 + 0.30 - 30.30)	30.30		Smt.	21513.00	
2	71.00	Demolition and disposal of unserviceable materials with all lead and lift. (i) Cement concrete. (Item used for old w.p. removal, if done previously) SOR It:- 20001B , p/169 + 1 % L.C. (383 + 3.83 = 386.83)	386.83		Cmt.	27464.93	
3	775.00	Providing and laying water proofing including 0.23 mts. radius vata with waterdrip as directed with 5 years written guarantee, by laying 40 mm thick cement mortar 1:4 (1 cement : 4 fine sand) after thoroughly cleaning the base slab and removing all the loose materials with wire brush, applying cement & waterproofing slurry evenly spread on slab and mixing water proofing materials in cement mortar in proportion as recommended by manufacture, laying brick bats after thoroughly soaked in water on layer of cement mortar, applying cement slurry on brick between @ 0.08 bag/smt. with mixing water proofing materials in proportion as recommended by the manufactures & finishing top with china mozaic tiles chips with 12 mm thick C.M. 1:3 base and laying by keeping gaps which should be filled with white cement and colour pigment including rounding or junction extending upto 15 cm along the wall, including curing etc. complete. Note : The measurement of	1206.95		Smt.	935386.25	

Sr. No	Quantity	Item Descriptions	Total Rate Including 1% Labour Cess		Per	Amount	
			₹.	Ps		₹.	Ps
		<p>this item shall be taken as that of the horizontal surface (length x width) that is from inside of the parapet walls, thus, not considering the surface measurement of the rounded vatas.</p> <p>As per R.A.+1% L.C. (1195 + 11.95 = 1206.95)</p>					
					Total Say	₹... ₹...	9,84,364.18 9,84,500.00

I/ We am/ are willing to carry out the work at _____ % above/below percent (should be written in figures and words) of the estimated rates mentioned above.

Amount of my/ our tender works out as under.

Estimated amount

Put to tender ₹. _____
Deduct _____% below ₹. _____
Net ₹. _____
In words _____

Estimated amount

Put to tender ₹. _____
Add _____% above ₹. _____
Total ₹. _____
In words _____

Note

1. All work shall be carried out as per Public Works Department Handbook and other specifications of PWD/CPWD/SVNIT or as directed.
2. All the columns is Scheduled be filled in ink and the total of the entries in the last column should be struck by the contractor under his signature.
3. Rates quoted include clearance of site (prior commencement of work and at its close) in all respects and hold good for work under all conditions, site, moisture, weather etc.
4. To be continued on additional sheets, if found necessary.

POSTAL ADDRESS OF CONTRACTOR

SIGNATURE OF CONTRACTOR

DATE: