



सरदार वल्लभभाई राष्ट्रीय प्रौद्योगिकी संस्थान, सुरत
Sardar Vallabhbhai National Institute of Technology, Surat



ESTATE SECTION

PERCENTAGE RATE TENDER PAPER



TENDER: 3

PRICE BID

Name of work	:	Construction of two Volleyball Courts at Student Activity Centre in SVNIT, Surat.
Name of Contractor	:	
Tender Fee	:	₹.500=00
Class of Registration	:	E1 – Class & Above
Issue of tender	:	29/11/2018 to 20/12/2018.
Receipt of tender	:	26/12/2018 upto 5:00 p.m.

The Director, S. V. National Institute of Technology, Ichchhanath, Surat – 395 007.

☎ 91-0261-2259571, 2259582-84

Name of Work :- Construction of two Volleyball Courts at Student Activity Centre in SVNIT, Surat.

**SCHEDULE – B
(PWD SOR 2015-16)**

Sr. No	Quantity	Item Descriptions	Total Rate Including 1% Labour Cess		Per	Amount	
			₹.	Ps		₹.	Ps
1	590.00	Excavation for foundation up to 1.5M depth including sorting out and stacking of useful materials and disposing of the excavated stuff upto 50 meter lead. (A) Loose /soft soil. SOR - 4.0.A, P-43+1%L.C (122.00 + 1.22 = 123.22)	123.22		Cmt.	72699.80	
2	1295.00	Rolling of earthwork in layers with power roller including filling in depression which occur during the process, with power roler 8 to 12 tonne. SOR - 26002.0, P-210+1%L.C (8.00 + 0.08 = 8.08)	8.08		Smt.	10463.60	
3	130.00	Filling in plinth with sand under floors including watering, ramming, consolidating and dressing complete. SOR.4007, P/41 + 1% L.C. (482.00 + 4.82 = 486.82)	486.82		Cmt	63286.60	
4	420.00	Supplying & Spreading the good quality of yellow soil with all lead & lift & including the cost of labour for spreading the soil as directed by the engineer incharge etc. comp. As per Market Rate+ 1% L.C. (420.00 + 4.20 = 424.20)	424.20		Cmt	178164.00	
5	1295.00	Rolling & consolidation of soling including filling in depression which occur during the process, with power roler 8 to 12 tonne. SOR - 26.76, P-216+1%L.C (17.10 + 0.17 = 17.27)	17.27		Smt.	22364.65	
6	253.00	Supplying & Spreading the good quality of red murrum/soil with all lead & lift & including the cost of labour for spreading as directed by the engineer incharge etc. comp. As per Market Rate+ 1% L.C. (620.00 + 6.20 = 626.20)	626.20		Cmt	158428.60	
7	1295.00	Rolling & consolidation of soling including filling in depression which	17.27		Smt.	22364.65	

Sr. No	Quantity	Item Descriptions	Total Rate Including 1% Labour Cess		Per	Amount	
			₹.	Ps		₹.	Ps
		occur during the process, with power roler 8 to 12 tonne. SOR - 26.76, P-216+1%L.C (17.10 + 0.17 = 17.27)					
8	253.00	Supplying & Spreading the good quality of red murrum/soil with all lead & lift & including the cost of labour for spreading as directed by the engineer incharge etc. comp. As per Market Rate+ 1% L.C. (620.00 + 6.20 = 626.20)	626.20		Cmt	158428.60	
9	1295.00	Rolling & consolidation of soling including filling in depression which occur during the process, with power roler 8 to 12 tonne. SOR - 26.76, P-216+1%L.C (17.10 + 0.17 = 17.27)	17.27		Smt.	22364.65	
10	68.00	Boring holes 1.0m deep in ordinary soil (for cast in situ piles) and getting out the soil and disposal of the surplus excavated soil as directed within a lead of 50 meter following diameter of piles (iii) 300 mm SOR - 4.27, P-42+1%L.C (250.29 + 2.50 = 252.79)	252.79		Each	17189.72	
11	5.00	Providing and laying cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) and curing complete excluding cost of form work (B) Independent piers, columns and pillars up to floor two level (upto 10 ton) SOR - 5.3.13B, P-47+1%L.C (3204.00 + 32.04 = 3236.04)	3236.04		Cmt.	16180.20	
12	576.00	Providing & Fixing 4.00 m High fencing with 75mm dia vertical G.I. post (B-class ISI)(5.0 mt. height) fixed at 2 metre centre to centre distance. Top, bottom and centre horizontal support of 25 mm diaG.I. pipe and G.I. chain link fencing of size 50 mm x 50 mm x 10 gauge with 4 metre height including fixing post, welding, two coats of primer and oil painting green colour including labour charges for welding,grinding & fixing the post in grouting in column etc complete. as per direction given by Engineer In-	1927.08		Smt	1109998.08	

Sr. No	Quantity	Item Descriptions	Total Rate Including 1% Labour Cess		Per	Amount	
			₹.	Ps		₹.	Ps
		charge. As per R.A.+ 1% L.C. (1908.00+19.08 = 1927.08)					
13	5.00	Providing & laying cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) and curing complete excluding cost of formwork work in (A) Foundation & Plinth. SOR-5.3.13(A) P-47+ 1% L.C. (3204.00 + 32.04 = 3236.04)	3236.04		Cmt.	16180.20	
14	144.00	Providing and fixing Pre Cast Concrete kerb stone of gray cement base conc. block 30 cm length, 30 cm height & 15 cm thick of M-250 grade conc. as per approved design & including excavation for fixing in proper line level, filling the joint with C.M. 1:3 (1 cement : 3 fine sand) etc., complete. SOR-14023, P-148+ 1% L.C. (242.00 + 2.42 = 244.42)	244.42		Rmt	35196.48	
			Total	₹...		19,03,309.83	
			Say	₹...		19,03,310.00	

I/ We am/ are willing to carry out the work at _____ % above/below percent (should be written in figures and words) of the estimated rates mentioned above.

Amount of my/ our tender works out as under.

Estimated amount

Put to tender ₹. _____

Deduct _____ % below ₹. _____

Net ₹. _____

In words _____

Estimated amount

Put to tender ₹. _____

Add _____ % above ₹. _____

Total ₹. _____

In words _____

Note

- All work shall be carried out as per Public Works Department Handbook and other specifications of PWD/CPWD/SVNIT or as directed.
- All the columns is Scheduled be filled in ink and the total of the entries in the last column should be struck by the contractor under his signature.

3. Rates quoted include clearance of site (prior commencement of work and at its close) in all respects and hold good for work under all conditions, site, moisture, weather etc.
4. To be continued on additional sheets, if found necessary.

POSTAL ADDRESS OF CONTRACTOR

SIGNATURE OF CONTRACTOR

DATE: